

2021 Paving Schedule

Updated: July 8, 2021

Road	Method	Start
Pocono Ridge Road	Mill and Pave	complete
Candlewood Lake Road	Mill and Pave	complete
Gurski Farm Driveway	Reclaim and Pave	in progress
Brookdale Lane	Reclaim and Pave	complete
Puritan Valley	Reclaim and Pave	complete
Meadowview Drive	Reclaim and Pave	in progress
Premium point	Reclaim and Pave	in progress
Old Turnpike (partial)	Reclaim and Pave	in progress
Long Meadow Hill Road (25 to Signal)	Mill and Pave	August 2021
Beachwood Circle	Reclaim and Pave	August 2021

Micro Surfacing scheduled Start May 15, 2021 - Complete

Merwin Brook Road (Manor to end)
Old Middle Road
Hop Brook Road

Scheduled for August 2021

Main Drive
Deer Run
Whippoorwill
Flax Hill (Whippoorwill to Cul de Sac)
Old Hemlock
Candlewood Lake Road (portions)

- Additional roads may be added as need and as the town budget dictates.

Method Descriptions

I. Reclaim and Pave

1. Mechanically grind existing pavement and sub-base to a depth of 6 to 8-inches to be used as the new sub-base material
2. Grade and compact the new sub-base
3. Install 1-1/2 inches of hot asphalt as the base layer
4. Install 1-1/2 inches of hot asphalt as the top course
5. Install curbing and driveway aprons as necessary

II. Mill and Fill

1. Mechanically grind the top course 1-1/2 inches of asphalt and haul it off site
2. Install 1-1/2 inches of hot asphalt as the new top course

III. Micro surface

The micro surface goes down as liquid slurry. It must set for 15-20 minutes prior to driving on.

1. Crack seal (usually done the year prior)
2. Install micro base course
3. Install micro top course

IV. Cold in Place Recycle with an Overlay

1. Mechanically grind emulsify and re-use the top 3 –inches of asphalt as the base
2. Install 1-1/2 inches of hot asphalt as the top course
3. Install curbs and driveway aprons as necessary