

2024 Paving List- last updated 3/1/2024- Tentative- budget dependent

Hot Asphalt

Road	from	to	Method	Status
Candlewood Lake Rd	Huck School	Elbow Hill	Mill and fill	April 2024
Candlewood Lake Road	North Mountain	Town Line	Mill and fill	April 2024
Grays Bridge	Stony Hill	Route 7 Bridge	Mill and fill	April 2024
Greenview Road	New Bridge Rd.	Town Line	Reclaim and Pave	Will be paved by New Milford DPW
Crestview Drive	Juniper	Cul de sac	Reclaim and Pave	Summer 2024
Cross Road	complete		Reclaim and Pave	Summer 2024
Huckleberry Hill	Old Federal	Rocky	Mill and fill	Summer 2024
The Following Roads will be paved by Aquarion Water Co.				
Knollcrest	Limits are to the extent of the water line installed in 2023			
Blueberry	complete			
Whipoorwill	complete			
Tower Road	Greenridge	Town Line	Reclaim and Pave	2024 (waiting on Aquarion to install water line)

Micro- surfacing- scheduled to start May 16th +/-

- Carmen Hill Road- Granite to Town Line
- North Mountain Road- Laurel to Flax Hill
- Overlook Drive- complete
- Riverford Road- Fall to #64
- Nabby Road – CLR to Town Line
- Pocono Road- Silvermine to Rt 25

Method Descriptions

I. Reclaim and Pave

1. Mechanically grind existing pavement and sub-base to a depth of 6 to 8-inches to be used as the new sub-base material
2. Grade and compact the new sub-base
3. Install 1-1/2 inches of hot asphalt as the base layer
4. Install 1-1/2 inches of hot asphalt as the top course
5. Install curbing and driveway aprons as necessary

II. Mill and Fill

1. Mechanically grind the top course 1-1/2 inches of asphalt and haul it off site
2. Install 1-1/2 inches of hot asphalt as the new top course

III. Micro surface

The micro surface goes down as liquid slurry. It must set for 15-20 minutes prior to driving on.

1. Crack seal (usually done the year prior)
2. Install micro base course
3. Install micro top course

IV. Cold in Place Recycle with an Overlay

1. Mechanically grind emulsify and re-use the top 3 —inches of asphalt as the base
2. Install 1-1/2 inches of hot asphalt as the top course
3. Install curbs and driveway aprons as necessary

